VIBRAWASTE · MUCKRAKER MR-5

Muckraker vs Conventional Septage Receiving Stations

How a stainless vibrating screen compares on cost, install, footprint and mobility

VIBRAWASTE

Pricing as of October 2026

Option	Equipment cost	Installation	Estimated cost before tax and freight	Truck unload	Footprint / infrastructure	Mobility
VibraWaste Muckraker MR-5 Stainless vibrating screen with dewatering auger	**$140,000***	Fixed or mobile option. Your site costs: pad, 240V hookup and discharge connection. About 1 hour from unload to first truck	$140,000 equipment price, plus tax, freight and your site costs	10-15 min (up to 400 GPM)	12' x 12' unit (20' x 20' work area) on a level concrete or gravel pad, or 6x6 / 8x8 treated timbers. Single-phase 240V, 2-pole 30A breaker, 50A plug. No 3-phase.	Fixed install or mobile: trailer-mountable with jacks on all four corners. Ships in two pieces.
Integrated drum screening station Screen, wash and compaction in one tank	From $350,000 (dual-truck version $700,000+)	$110,000 to $300,000	Starting price plus estimated installation: from $460,000 (dual-truck $810,000+)	5-10 min	Permanent installation at the plant; engineered site work	Fixed install
Rotary sieve unit Enclosed screening unit	From $289,000	$110,000 to $300,000	Starting price plus estimated installation: from $399,000	About 15 min	Permanent installation; no separate rock trap, grinder or receiving tank	Fixed install
Full-system receiving station Screening plus flow metering and hauler authentication	From $349,000	$110,000 to $300,000	Starting price plus estimated installation: from $459,000	Not published	Permanent installation; metering, controls, transaction tracking, grinder and screening	Fixed install
Configurable receiving station Built-to-order package	From $225,000	$110,000 to $300,000	Starting price plus estimated installation: from $335,000	Not published	Permanent installation; unloading connections, pretreatment, sampling, monitoring, access control	Fixed install
Access-control pedestal Hauler access and tracking only	From $189,000	$110,000 to $300,000	Starting price plus estimated installation: from $299,000	N/A (no screen)	Requires screening already in place at the plant	Fixed install

Competitor figures are published starting prices (October 2026). The $110,000 to $300,000 installation range is a VibraWaste estimate. *Muckraker price is for pickup at our Oklahoma fabrication shop. Sales tax, freight and your site costs are extra. Pricing subject to change.

These products are not equal in features. The Muckraker does not include flow metering, hauler authentication, transaction tracking, a grinder or a receiving tank. The access-control pedestal has no screen.

Jon Jouvenaux, VibraWaste | jon@vibrawaste.com | (479) 425-1307 | vibrawaste.com
4149 Cook Rd #1, Bentonville, AR 72713 · *It's only waste if we waste it.*

What comes standard on the Muckraker

- Stainless steel construction; 3/16 in. stainless perforated screens
- Auger squeezes water out of trash and debris before disposal
- Two OLI vibratory motors, backed by OLI's own 24-month motor warranty
- No factory commissioning or startup crew needed. Your electrician hooks up the 240V circuit, and local permits may apply.
- Vibrating basket screens up to 400 GPM, no hand raking
- Hopper and auger hood safety interlocks
- About 14 amps running draw on single-phase 240V; 25 ft cord included
- Screened liquid goes to a frac tank, lagoon, receiving tank or approved sewer where permitted

Why it matters

For haulers. Trucks unload in 10-15 minutes and get back on the route instead of waiting on a hand-raked bar screen. You can put the screen on your own pad or depot, close to where you pump, and trailer-mount it to follow the work. Trash comes off compacted and dewatered, so you stop hauling water.

For plants. Screen hauled waste before it reaches pumps and headworks. The Muckraker runs on a single-phase 240V, 50A RV-style hookup, so there is no three-phase power run, and it can be paired with access-control equipment a plant already has.

For budgets. Published starting prices for the stations in the table range from $189,000 to $700,000 or more before installation, and our estimate for installation is $110,000 to $300,000. Financing may be available through DealerDog, a third-party lender, subject to credit approval. DealerDog sets its own terms and credit review process.

Jon Jouvenaux, VibraWaste | jon@vibrawaste.com | (479) 425-1307 | vibrawaste.com
4149 Cook Rd #1, Bentonville, AR 72713 · *It's only waste if we waste it.*